

## 1.0 **GENERAL**

### 1.1 **Scope**

- .1 This guideline addresses the materials, methodology and services necessary for complete installation of sodded lawns, which includes the control of noxious and pernicious weeds within seeded lawns and meadows.
- .2 Due to the current prevalence of damages associated with Chaffer Beetle, the scope of sod installation should be limited if not suspended where practical in favour of seeding with resistant seed mixtures, or designing with alternate groundcover or planting. See Section 32 92 00, Turf and Grasses, 2.6.3.2.

### 1.2 **Related Work**

- .1 Related Work in Other Sections:
  - .1 Section 32 80 00 Irrigation
  - .2 Section 32 91 00 Planting Preparation
  - .3 Section 32 93 00 Plants
  - .4 Section 32 92 00 Seeded Lawns and Meadows

### 1.3 **Pertinent Standards and Legislation**

- .1 Conform to the requirements of the latest editions of the following standards and legislation:
  - .1 Canadian Landscape Standard – Current Edition
  - .2 British Columbia Standard for Turfgrass Sod
  - .3 British Columbia Weed Control Act
  - .4 Canada Seed and Fertilizer Act
  - .5 Canada Pest Control Products Act

### 1.4 **Inspections and Approvals**

- .1 Notify Landscape Architect (Municipal Services) at least forty-eight (48) hours before final review of sod is required.
- .2 For [acceptance by Municipal Services](#), all lawns and meadows must be alive and in a healthy, satisfactory growing condition at the time of inspection.

## 2.0 **MATERIALS AND DESIGN REQUIREMENTS**

### 2.1 **General**

1. Avoid creation of convoluted lawn areas that are less than 2 m wide, end in very narrow angles, punctuated with obstacles, or are oddly shaped that make servicing with riding mowers impossible. Boulevards or medians 2 m wide or less must be planted.

### 2.2 **Warranty**

- .1 All workmanship and materials covered in this Section shall be warranted for a period of one (1) full year from the date of Substantial Completion.

## 2.3 Materials

- .1 Sod:
  - .1 Sod shall be nursery grown turfgrass sod, true to type, conforming to the B.C. Standard for Turfgrass Sod. Only "Non-Netted" Sod will be accepted.
  - .2 The quality grade of sod (based on B.C. Standard for Turfgrass Sod) shall be No. 1 Premium Grade grown on a screened alluvial sand base, cultivated on a sterilized soil base to ensure a weed free product. The maximum fines (silt and clay) in the alluvial sand base to be no more than 1% by weight.

Sod to be:

  - .1 'Supreme' (30% Kentucky Blue, 30% Fescue, 40% Perennial Rye) as grown by Anderson Sod Farm, 10821 Farms Road, Mission, B.C., 604-826-2383.
  - .2 Or approved equal. Equivalency to be reviewed and approved by Head Landscape Technologist (UBC Municipal Services).
- .2 Weed Control: the use of toxic pesticides for cosmetic purposes is voluntarily suspended on UBC Campus. Manual weed control is the preferred method and may be the only permitted methodology. Remove and replace significantly affected sod. Consult with Head Landscape Technologist (UBC Municipal Services) for approval of any alternative organic weed control substances or methodologies.

## 2.4 Subgrade Preparation and Finishing

- .1 Obtain Project Landscape Architect approval of subgrade and growing medium prior to laying any sod.
- .2 Ensure finish grade surfaces are tamped with roller before laying sod, and finish grades are congruent with project drawings as specified.
- .3 Grades:
  - .1 Sodded lawns must be graded at slopes safe for mowing by maintenance crews and safe for all other Campus users. Maximum allowable slope for lawns is 5:1. Slopes over 5:1 are only permitted where pre-approved by Landscape Architect (UBC Municipal Services). (See also Section 31 22 00 Grading, 1.1.1). Areas to be sodded shall be at grades as shown at the time of sodding, less an allowance for the thickness of the sod.
  - .2 Crown or slope for surface drainage and eliminate all low spots or depressions.
- .4 If the surface of the growing medium is dry, lightly moisten the growing medium immediately prior to laying sod.

## 2.5 Sod Laying

- .1 Use full rolls where possible. No bits or sod remnants are allowed.
- .2 Only lay sod within acceptable weather conditions during March through mid-October. Do not lay sod during periods of high summer temperatures, or drought when no consistent, supplementary irrigation is available to retain sod and underlying medium in moist condition.

- Do not lay sod during periods of heavy rainfall and when excessive puddling is apparent on site.
- .3 Lay sod in rows with ends staggered. Butt all sections closely. Do not overlap or allow gaps wider than 2mm between sections. Top of sod to be flush with adjacent walking surfaces.
  - .4 Protect new sod from heavy foot traffic during laying. Place planks or plywood if necessary to prevent damage. Lay within 24 hours after delivery to prevent deterioration.
  - .5 Lay sections on slopes at right angles to the direction of the slope. Stake sod into place with wood stakes driven flush with the surface in any locations having slopes steeper than 3:1 (NOTE: Sloped lawns over 3:1 are only permitted where pre-approved by Head Landscape Technologist (UBC Municipal Services). Interval spacing on stakes shall not exceed 500mm. Prior to pedestrian traffic being allowed onto the sod, and only after the sod is well rooted into the growing medium, pegs or stakes shall be removed or driven to an elevation 50mm below the finished surface.
  - .6 Cut sod where necessary only with sharp tools.
  - .7 Water thoroughly to penetrate the full depth of the growing medium as specified.
  - .8 When sod has dried sufficiently, roll with 113kg. (250lb.) roller to obtain smooth uniform surface and ensure a good bond between soil and sod.
  - .9 Erosion control netting shall be installed in sodded areas where required, erosion control mesh or netting shall be placed and secured with stakes or staples set firmly into the ground to a minimum depth of 150mm. Spacing of stakes or staples shall be adequate to ensure complete anchorage of the sod to the ground.

## 2.6 Maintenance

- .1 The maintenance period begins at the time sod is laid and continues [until successful establishment of the lawn and acceptance by Municipal Services](#)
- .2 Maintenance shall consist of all measures necessary to keep grass healthy, in a vigorous growing condition and well rooted into the underlying soil.

\*\*\*END OF SECTION\*\*\*